## Installation:

1st nut should be spanned with 40 - 45Nm.

2nd nut should shall be brought at least to a snug-tight condition, with special care being given to avoid over-tightening. Nut-marking should be made acc. to figure after torque.


## Maintenance:


Visual inspection of bolt torque and any loose items is made 1 year after installation, and afterwards every 5th year.

Check if the marking from bolt torque is still straight.

Check if the corrosion protection system is satisfactory.

Any findings must be repaired as soon as possible.





2nd nut control line

Max loads per 1 mount pole from equipment: 150kg, CxA=1.6m2

ITEM NO.	PART NUMBER	DESCRIPTION	QTY.
2	CB-L120-180 300	C bracket L120-180	4
3	CVB_H400	Horizontal pole for C and V bracket - Vertical Ø60,3-76,1	2
4	U-bolt M12 C-C = 90		4
5	Washer ISO 7089 - 12		40
6	ISO 4017 - M12 x 45-N		8
7	ISO - 4032 - M12 - W - N		32
8	ISO - 4035 - M12 - N		32
9	M12x280 DIN976	Horizontal pole bracket pin-bolts	8
10	Pole Ø76-2500	Vertical pole Ø76,1 - length: 2500	1
11	GL 76x1.6-4	tubular legs for Ø76,1	2

Rev.:	Int.:	Date:		Comment									
	X	Customer.:											
		Subjekt.:	Ante	nna offs	et f.	L120	180	with					
<b>X</b>		Date.:	24-06-	2020	Pr	oduction n	0.:			Scale.:	1:15		Format:A3
0	A/ST	Order no.:			Ca	alculation:				Int.:	SP/MRF		Projektion:
Ca	Drawing. No.: CB-L120-180 H400 Note.:									Tolerance: DS/EN 1090-2			
This drawing is our property and must not be copied, transfered or in any way used by a third party without our written permission  DS/ISO 2768-2-L													
Carl C	A/S M	anufacturing	Engine	ering Comme	rc Sme	devej 2	DK-6900	Skjern	Tel. +45	97351	1066 Fax +45	9735127	6 www.carl-c.com