## Installation:

1st nut should be spanned with 40 - 45Nm.

2nd nut should shall be brought at least to a snug-tight condition, with special care being given to avoid over-tightening. Nut-marking should be made acc. to figure after torque.


## Maintenance:


Visual inspection of bolt torque and any loose items is made 1 year after installation, and afterwards every 5th year.

Check if the marking from bolt torque is still straight.

Check if the corrosion protection system is satisfactory.

Any findings must be repaired as soon as possible.





Max loads per 1 mount pole from equipment: 100kg, CxA=1.0m2

ITEM NO.	PART NUMBER	DESCRIPTION	QTY.
2	WB_Ø193- 244_H150_V170	Horizontal W bracket Ø193-244 with vertical pole Ø76,1	3
3	GL 76x1.6-4	tubular legs for Ø76,1	6
4	Washer ISO 7089 - 12		12
5	ISO - 4032 - M12 - W - N		6
6	ISO - 4035 - M12 - N		6
7	ISO 4017 - M12 x 110-N		6

Rev.:	Int.:	Date:	(	Comment									
	大	Customer.:	·										
	4	Subjekt.:	Anter	nna offs	et f.	Ø19.	3-244	with			•		
<b>X</b>		Date.: 2	3-06-2	2020	Pi	roduction r	10.:			Scale.:	1:5		Format:A3
0	A/ST	Order no.:			C	alculation:				Int.:	SP/MRF		Projektion:
Ca	Drawing. No.: WB_Ø193-244_H150									Tolerance: DS/EN 1090-2			
This drawing is our property and must not be copied, transfered or in any way used by a third party without our written permission  DS/ISO 2768-2-L													
Carl C	A/S M	anufacturing E	ingineer	ring Commer	c Sme	edevej 2	DK-6900	Skjern	Tel. +45	97351	066 Fax +45	5 9735127	76 www.carl-c.com